MISCELLANEOUS DEPARTMENTS.

DEPARTMENT OF AGRICULTURE ENGINEERING SECTION.

Notification.

Notice is hereby given that sealed tenders will be received at the office of the Agricultural Engineer, up to 2 P.M., on 6th April 1929, for constructing a cotton laboratory on the Government Experimental Farm, Babbur 3 miles from Hiriyur. An approximate estimate of quantities is given below. The quantities are not guaranteed. The work should be completed by the end of May 1929.

2. Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3. Each tender must be accompanied by a deposit of rupees one hundred in cash or as earnest money in default of which, tenders will be rejected.

4. Subject to the final sanction of the Director of Agriculture, acceptance of any tender will rest on the Agricultural Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

5. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

6. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract showing the quantities for the construction of the cotton laboratory on the Babbur Farm.

No.	Items of work	Per unit	Quantity
1	Earthwork excavation for foundation	C.yd.	101
2	Concrete in mortor	„	1,362
3	Rough stone in lime mortor	C.ft.	1,565
4	Brick in mud in Superstructure	„	2,219
5	Brick in lime in do	„	443
6	Cut stone dressed	S.ft.	160
7	Iron trusses	Cwt.	6·6
8	M. S. Angle 1½″ x 1½″ x ¼″ purlins	„	4·14
9	M. S. Ice 2″ x 2″ x ¼″ rafters	„	2·62
10	Iron girders 1½″ x ¼″ bressumer	„	2·46
11	Roofing with corrugated iron sheeting with thatch on top ...	Qrs.	20·6
12	Stone pillars 1½″ x 6″ thick	Sq.ft.	75
13	Doors penelled including fitting, etc., complete	S.ft.	96
14	Windows panelled outside and glassed inside without iron bars.	„	193
15	Top windows with glass panes fitted complete ...	„	25
16	Flooring with Cudappah slabs on concrete	Sqr.	14·00
17	Painting doors and windows	Qrs.	6.9
18	Plastering with chunam and white washing	Sqr.	51·5
19	Filling with earth	C.yd.	96

M. G. SINGRACHAR,
Agricultural Engineer.

DEPARTMENT OF AGRICULTURE, MYSORE STATE.

OFFICE OF THE VICE-PRINCIPAL IN-CHARGE, GOVERNMENT EXPERIMENTAL FARM, HEBBAL.

Abstract Notification dated the 18th March 1929.

The attention of the public is invited to the Notification calling for Tenders for the purchase of jaggery manufactured on the Hebbal Farm, published in page 293, Part VI of the *Mysore Gazette*, dated the 14th March 1929.

GUNDAPPA S. KURPAD,
Vice-Principal in-charge.